

Seismic Evaluation Report

Project: Template project name Project No. xxx-xx
Location: Template site address Date: day-mo-yr
Client: Template client name Report No. x
Reported by: Template staff name Distribution: x

Comments

We have reviewed the installation of the 75 kva Transformer located at xxxx, Renfrew, Ontario.

We are satisfied that the new transformer including their attachments have been carried out in an acceptable manner.

Based on this structural review we confirm that the work is in compliance with the 2012 Ontario Building Code including seismic restraint.

Photograph 1

- View of the transformer suspended with threaded rods and Unistrut framing connected to the wall.



Photograph 2

- Typical view of the threaded rod hangers for the transformer.
- Hangers are connected to Unistruts between open web steel joists.



Photograph 3

- View of the open web steel joist with Unistrut.



Photograph 4

- View of threaded rod with unistrut.



Should you have any questions regarding this report please contact the undersigned.

LEEKOR Engineering Inc.,

XXXX

Sep. 14/23